## 24 Foot Stock Production Trailers



Fully Finished Inside & Out • Dual Suite - 1-Front / 1-Rear • Heat & AC • 6 Racks Console • I/O Panel • Carpeted • Track Lighting • Breaker Panel w/Generator Input

## VPTR-24 Standard Features • 24 Foot Dual Suite Model

- Dexter Torflex Twin Axles (2x 5,200 Lb.)
- 24 Foot x 8.5 Foot
- White Aluminum Rivetless Exterior (Colors Available) 2x 13,500 BTU Roof AC / Heat Strip Units
- Climate Controlled
- 2 Separate Locking Suites
- Generous 80" Interior Head Room
- Deluxe 'Control Room' Interior
- Exterior Quartz Light
- Dual Rear Stabilizer Jacks
- Rear Bogey/Skate Wheel "Bottom Out" Protection
- Optional Spare Tires Available

- Fully Insulated Walls & Ceiling
- Premium Radial Tires & Gray Mods
- 1x 13,500 BTU Equipment Rack AC Unit
- 36" Lockable Passenger Door
- 40" Lockable Rear Door
- Six 19" Racks @ 37RU & Two @7RU
- Breaker Box w/ Generator Input
- I/O Panel & Cable Hatches
- Tows Easily With any Class 3 Hitch

## **VPTR-24 Specifications**

**OVERALL LENGTH:** 27'-10"

**OVERALL WIDTH:** 102" **OVERALL HEIGHT:** 106"

**INTERIOR LENGTH:** 23'-11" **INTERIOR WIDTH:** 98"

80" **INTERIOR HEIGHT:** 

**DUAL TANDEM AXLE DESIGN:** 

**HITCH BALL SIZE:** 2 5/16

**USABLE RU ABOVE COUNTER:** 18RU(x5)

**USABLE RU BELOW COUNTER:** 

Forward: #1: 7RU • #2-4: 13RU • #5: 6RU

#6: 37RU • #7&8: 7RU Aft: MAIN COUNTER TOP SIZE: 8' x 24" WORK COUNTERS: Forward: 30" x 48" (2x)

> Aft: 28" x 36" (1x)

**ELECTRICAL CAPACITY AT PANEL:** 

220/60AMPS Single Phase • 30 AMPS per leg

Additional Payload Capacity By Axle:

(Standard/Stock x2): 5200/4600+ Lbs. Approx.

Optional Axles Avail. 6000/6500+ Lbs. Approx.

7000/8500+ Lbs. Approx. 8000/10500+ Lbs. Approx.

Note: Weights based on absolute maximum gross weights. Please include the racks, furniture and equipment to calculate the maximum cargo/payload deployed weight. It MUST not exceed the axle payload number.

Options: Custom Builds are available.

## **Model VPTR-24**